Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Division

Name of Work: Emergency Grants Works in Ward no 03, Attur.

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300 1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	150.44	261.00	Rupees Two Hundred Sixty One Only
2	KSRB 2-1 : Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be	Cum	42.88	393.00	Rupees Three Hundred Ninety Three Only
3	KSRB 4-1.6 , Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	25.50	6005.00	Rupees Six Thousand Five Only
4	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M20 for R.C.C works laid in 15 cms thick layers and well compacted by vibrating, curing, for foundations & sub-structure works with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.)	Cum	52.32	6030.00	Rupees Six Thousand Thirty Only
5	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications.	Ton	3.34	78610.00	Rupees Seventy Eight Thousand Six Hundred Ten Only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.	Sqm	187.06	397.00	Rupees Three Hundred Ninety Seven Only
7	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading etc., complete as per the direction of engineer in charge	Sqm	247.14	2442.00	Rupees Two Thousand Four Hundred Forty Two Only

	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
E1	Providing and fixing RCC precast cover slab of 250mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	20.30	5662.89	Rupees Five Thousand Six Hundred Sixty Two And Paise Eighty Nine Only

Executive Engineer
Yelahanka Division
BBMP